



Purchasing Department

Ste. #310 - City Hall
1301 Bacharach Blvd.
Atlantic City, NJ 08401-4603
Phone (609) 347-5390
Fax (609) 347-5250

To: All Prospective Bidders

From: Mary P. Mooney, Purchasing Agent

Date: 9/17/2020

RE: **ADDENDA #1** BID #20-31 CASPIAN POINTE PEDESTRIAN &
BICYCLE CONNECTION FEDERAL PROJECT # TAP-1011 (300)
CONSTRUCTION NJDOT JOB #5502324

**PLEASE AFFIX REVISED BID SCHEDULE PAGE 74 TO YOUR BID PACKAGE &
COMPLETE/RETURN WITH YOUR BID SUBMISSION.**

1. Question: The sidewalk detail also has a turn down slab. Is this throughout the entire length of sidewalk and on both sides as shown on C-8 & C-9 of plans.

Answer: Turn down slab detail F-F is only required at the northerly end of the site, where the F-F section line is drawn.

2. Question: The wire mesh is called for to be epoxy coated but the rebar in the turn down slab does not. Please confirm this is correct

Answer: All rebar shall be epoxy coated for the project.

3. Question: What is the railing material? Schedule 40 pipe can be many different things.

Answer: Railing is Aluminum, and shall match Atlantic City Boardwalk Railing utilized on the recently Constructed Boardwalk Ramps at Atlantic Avenue & Oriental Avenue.

4. Question: There are no finish or existing grades on the plans. How did you calculate the fill material needed?

Answer: Existing contours are shown on the documents. Proposed elevations of the slabs are also shown on the documents. Fill was calculated based on existing project conditions.

5. Question: What is the finish of the concrete?

Answer: Match finish of existing concrete splash pad

6. Question: Will the splash pad be constructed prior to our work commencing?

Answer: Splash pad is completed.

7. Question: What is the anticipated start date of construction?

Answer: TBD

8. Question: Are permits needed?

Answer: Electrical permit shall be required at a minimum. Bidder is responsible to apply for and obtain all permits.

9. Question: Specs call for an office trailer. If this is required it should be part of the bid sheet.

Answer: Trailer is required – See Attached Revised Bid Schedule Page 74

10. Question: Specs call for Project ID Sign. There is no line item for this on the bid sheet.

Answer: ID sign is required - See Attached Revised Bid Schedule Page 74

11. Question: Specs call for 6' High fence around site. There is no line item for this on the bid sheet. Does this apply?

Answer: Fence is required - See Attached Revised Bid Schedule Page 74

12. Question: Bollards. Plan detail shows Steel Dome Welded. Bid Sheet says Concrete. Which is it? These are two different products.

Answer: Bollards shall be per detail on drawings – Bid Schedule Page 74

13. Question: Electrical plan shows all circuit conduits going through all light standards, and does not show any junction boxes. Light standard foundations are not large enough to handle entry/exit of all circuit conduits, and length of circuits are too long not to include junction points. Please advise.

Answer: We show no more than one conduit entering and one conduit exiting any one pole base on the drawings. The largest pair of PVC conduits that are show entering/leaving light pole base are 1". Drawings show a 24" round underground concrete light pole base. There should be no problem making the specified two (2) 1" conduits entering/leaving work. We have no problem with the contractor installing pull boxes, (not junction boxes), along the underground route for the longer wiring runs. An acceptable underground pull box is a UL listed, Quazite underground enclosure constructed of pre-cast polymer concrete reinforced with fiberglass, with a Tier 22 rating and gasketed cover labeled as electric. All pull boxes should be sized per the requirements listed in the 2018 National Electric Code and should have their gasketed covers installed flush to grade.

Thank you for your cooperation.

**CITY OF ATLANTIC
ATLANTIC COUNTY, NEW JERSEY
CASPIAN POINTE PEDESTRIAN & BICYCLE CONNECTION
FEDERAL PROJECT # TAP-1011 (300) CONSTRUCTION NJDOT JOB #5502324**

C. REVISED BID SCHEDULE

NJDOT Job No. 5502324
Federal Project No. TAP-1-11(300) Construction

Item	Description	Unit	Quantity	Price	Total
1	PERFORMANCE BOND AND PAYMENT BOND	LS	1		
2	MOBILIZATION	LS	1		
3	CONSTRUCTION LAYOUT	LS	1		
4	SILT FENCE	LF	1,500		
5	CONSTRUCTION DRIVEWAY	LS	1		
6	INLET FILTER	EA	4		
7	FINAL CLEANUP	LS	1		
8	SITE CLEARING	LS	1		
9	REMOVAL OF PAVEMENT	SY	4,200		
10	SOIL AGGREGATE BASE COURSE, VARIABLE THICKNESS	CY	7,700		
12	REINFORCED CONCRETE SIDEWALK 4" THICK (WITH TURN DOWN)	SY	4,620		
12	DETECTABLE WARNING SURFACE	SY	10		
13	6" CONCRETE VERTICAL CURB	LF	50		
14	GUIDE SIGNS, BREAKAWAY SUPPORTS	SF	24		
15	LIGHT STANDARD FOUNDATION, FURNISH & INSTALL	EA	29		
16	LIGHT STANDARD, ALUMINUM, FURNISH	EA	29		
17	LIGHT STANDARD, ALUMINUM, INSTALL	EA	29		
18	LUMINAIRE, FURNISH	EA	58		
19	LUMINAIRE, INSTALL	EA	58		
20	ELECTRICAL SYSTEM FOR LIGHTING, FURNISH & INSTALL	LS	1		
21	PREPARATION OF EXISTING SOIL FOR LANDSCAPING	SY	1,160		
22	SITE FURNITURE, BENCHES, FURNISH & INSTALL	EA	16		
23	ROADWAY STRIPING	LF	400		
24	HAND RAILING	LF	200		
25	STEEL BOLLARDS	EA	12		
26	TRASH RECEPTACLES, FURNISH & INSTALL	EA	8		
27	RECYCLE RECEPTACLES, FURNISH & INSTALL	EA	8		
28	TOPSOIL	CY	1,200		
29	GRASS SEED	SY	6,750		
30	STRAW MAT EROSION CONTROL	SY	6,750		
31	AMERICAN BEACH GRASS, FURNISH & INSTALL	EA	2950		
32	SITE CONSTRUCTION TRAILER	EA	1		
33	PROJECT IDENTIFICATION SIGN	EA	1		
34	SITE FENCING	LF	1500		
	SUBTOTAL				
	OWNER'S CONTINGENCY ALLOWANCE			\$25,000.00	\$25,000.00
	PROJECT TOTAL				