

BID FORM

Pursuant to and in compliance with your Advertisement for Bids and the Information for Bidders relating thereto, the undersigned hereby offers to furnish all plant, labor, materials, supplies, equipment and other facilities and things necessary for, or proper for, or incidental to the ATLANTIC AVENUE ROAD DIET, PHASE 1, in accordance with the applicable provisions of plans and specifications and all addenda issued by Atlantic City or its Engineer prior to the date of opening the bids, whether received by the undersigned or not, for the amount bid based on the following unit and/or lump-sum prices:

NOTE: Extension of Unit Prices must be exact.

BASE BID

Item	Quantity	Units	Description	Unit Price	Amount
1	1	LS	CLEARING SITE	\$	\$
2	1	ALLOW	UNIFORM POLICE TRAFFIC DIRECTOR	\$ 75,000.00	\$ 75,000.00
3	200	UN	DRUM	\$	\$
4	200	UN	TRAFFIC CONE	\$	\$
5	600	SF	CONSTRUCTION SIGNS	\$	\$
6	43800	SY	HMA MILLING, 3" OR LESS	\$	\$
7	5125	TON	HMA 12.5M76 SURFACE COURSE, 2" THICK	\$	\$
8	1035	SY	CONCRETE SIDEWALK, 4" THICK	\$	\$
9	80	SY	DETECTABLE WARNING SURFACE	\$	\$
10	1415	LF	9" X 18" CONCRETE VERTICAL CURB	\$	\$
10A	1045	SY	CONCRETE GUTTER, 2' x 8"	\$	\$
11	34148	LF	TRAFFIC STRIPES, 4"	\$	\$
12	2755	LF	TRAFFIC STRIPES, 6"	\$	\$

Item	Quantity	Units	Description	Unit Price	Amount
13	8725	LF	TRAFFIC STRIPES, 8"	\$	\$
14	7180	LF	TRAFFIC MARKINGS LINES, 24"	\$	\$
15	2880	SF	TRAFFIC MARKINGS SYMBOLS	\$	\$
16	12	UN	RESETS CASTINGS (IF & WHERE DIRECTED)	\$	\$
17	10280	LF	TRAFFIC SIGNAL CABLE, 5 CONDUCTOR	\$	\$
18	4120	LF	TRAFFIC SIGNAL CABLE, 10 CONDUCTOR	\$	\$
19	24	UN	ADJUST EXISTING SIGNAL HEAD	\$	\$
20	4200	LF	SERVICE WIRE, NO. 6 AWG	\$	\$
21	8500	LF	GROUND WIRE, NO. 8 AWG	\$	\$
22	2700	LF	GROUND WIRE, NO. 10 AWG	\$	\$
23	16900	LF	MULTIPLE LIGHTING WIRE, NO. 6 AWG	\$	\$
24	4800	LF	MULTIPLE LIGHTING WIRE, NO. 8 AWG	\$	\$
25	500	LF	MULTIPLE LIGHTING WIRE, NO. 10 AWG	\$	\$
26	161	UN	LIGHT POLE ASSEMBLY (LPA)	\$	\$
27	161	UN	CROSS BRACKET (CB)	\$	\$
28	264	UN	LUMINAIRE DECORATIVE L (53W)	\$	\$
29	58	UN	LUMINAIRE DECORATIVE EXISTING L (EX) REMOVAL & REINSTALL	\$	\$
30	30	UN	REMOVAL OF EXISTING POLE BASE AND POLE	\$	\$
31	17	UN	CONTROLLER TURN-ON	\$	\$

Item	Quantity	Units	Description	Unit Price	Amount
32	0	-	NO ITEM	\$	\$
33	0	-	NO ITEM	\$	\$
34	28	UN	18" X 36" JUNCTION BOX	\$	\$
35	3000	DOL	ASPHALT PRICE ADJUSTMENT	\$ 1.00	\$ 3,000.00
36	2000	DOL	FUEL PRICE ADJUSTMENT	\$ 1.00	\$ 2,000.00
37	0	-	NO ITEM	\$	\$
38	9000	LF	1 1/4" RIGID METALIC CONDUIT	\$	\$
39	210	LF	1 1/2" RIGID METALIC CONDUIT	\$	\$
40	215	LF	1" RIGID METALIC CONDUIT	\$	\$
41	7	UN	FOUNDATION TYPE 2M	\$	\$
42	7	UN	METER CABINET TYPE 2M	\$	\$
43	20	SY	DECORATIVE BRICK PAVERS	\$	\$
44	128	SF	REGULATORY AND WARNING SIGNS	\$	\$
45	2540	LF	RUMBLE STRIPS	\$	\$
46	17	UN	GPS TIMECLOCK	\$	\$

**TOTAL CONSTRUCTION COST, BASE BID Items
#1 - #46, Inclusive**

\$ _____

TOTAL AMOUNT BASE BID WRITTEN OUT

ALTERNATE BID NO. 2

Item	Quantity	Units	Description	Unit Price	Amount
47	6300	LF	FIBER OPTIC CABLE TYPE G	\$	\$

**TOTAL CONSTRUCTION COST, ALTERNATE
BID NO. 2 ITEM #47, INCLUSIVE**

\$ _____

TOTAL AMOUNT ALTERNATE BID 2 WRITTEN OUT

ALTERNATE BID NO. 1

Item	Quantity	Units	Description	Unit Price	Amount
48	6300	LF	CONCRETE ENCASED TELECOMMUNICATIONS CONDUIT 2 4"	\$	\$
49	2920	LF	CONCRETE ENCASED TELECOMMUNICATIONS CONDUIT 2' CONDUIT	\$	\$
50	15	UN	TELECOMMUNICATION VAULT 30 X 60	\$	\$
51	50	UN	ITS JUNCTION BOX TYPE C 24 X 36	\$	\$

**TOTAL CONSTRUCTION COST, ALTERNATE
BID NO. 1 ITEMS #48 - #51, INCLUSIVE**

\$ _____

TOTAL AMOUNT ALTERNATE BID 1 WRITTEN OUT

SIGNATURE

NAME & TITLE

BID DATE

COMPANY NAME